

Our Ref AMP/14862CO/71/AMP

12 June 2020

London Borough of Hackney
Hackney Service Centre
1 Hillman Street
Hackney
London
E8 1DY

ASHBURNHAM HOUSE
1 MAITLAND ROAD
LION BARN ESTATE
NEEDHAM MARKET
SUFFOLK
IP6 8NZ

Telephone (01449) 723 723

Fax (01449) 723 907

www.rsa-geotechnics.co.uk



RSA GEOTECHNICS LTD

For the attention of Mr Stuart Dunlop, Pollution Control Officer

By Email only –
stuart.dunlop@hackney.gov.uk

Dear Stuart

**STONE STUDIOS, 80 TO 84 & 88 WALLIS ROAD, HACKNEY WICK E9 5LN
- RADIELLO CARTRIDGE AIR MONITORING FOR VOC & SVOC**

This letter reports the findings of the seventy-first round of air monitoring around the boundary of the above site by RSA Geotechnics Limited, at the request of Telford Homes PLC. Following the continuous monitoring undertaken during the bulk excavation of the basement areas of the site between May and September 2019, the monitoring was paused on cessation of earthworks. The monitoring recommenced on 28 October 2019, in advance of the remaining earthworks to be undertaken in the corridor area between the two basements; these works started on 18 November 2019. Excavation works were paused from 4 December 2019 to evaluate the control of groundwater and were re-started on 29 January 2020. Significant excavation works ceased on 28 February, with a single day of works undertaken on 18 March. Following closure of the site as a precautionary step with respect to the Covid-19 pandemic in March 2020, the site re-opened on 4 May 2020 with corridor excavation works recommencing on 11 May.

The monitoring detailed in this report covers the period between 22 May and 1 June 2020, during which time the final excavation works were in progress in the corridor area between the two basements.

1. Introduction

Earlier investigation of the site identified the potential for significant odour/vapour release during development. CFA piling works brought to surface hydrocarbon contaminated soils, as identified within the earlier site investigation. Some odours were reported, and odour/vapour issues were more pronounced during the initial bulk excavation phase for basement construction for Block A in September 2018; these works were ceased due to odour issues at that time.

Bulk earthworks recommenced under a new methodology on 7 May 2019. A detailed programme of daily site monitoring was maintained during these works, including continuous PID monitoring on the site boundary and on Wallis Road, as well as sampling and testing of ambient air to confirm concentrations are acceptable. This is supplemented by passive monitoring at the site boundary and in the surrounding area, as detailed in this report, which is reported on a nominal weekly basis.

Radiello 130 passive diffusive sampling tubes are installed at five locations around the perimeter of the site, at two residential receptor locations to the west and north of the site, and on the boundary of Mossbourne Academy School to the east of the site. This monitoring enables measurement of time-weighted average concentrations of BTEX, VOC and SVOC. Testing for speciated total petroleum hydrocarbons (TPH) is also undertaken, for two locations on the site boundary (Locations T1 and T2) and one location at the school (Location T3). Monitoring locations are as illustrated on drawing number 14862CO/2 Version B. As above, this passive longer-term monitoring is supplemented by additional monitoring and sampling in 'real-time' during active works on site.

Key volatile constituents of the contamination at the site were considered to be benzene and naphthalene, and these compounds have been adopted as markers for the initial assessment of contamination.

Initial assessment was undertaken adopting the EH40 Workplace Exposure Limit (WEL) for 8 hour time-weighted average (TWA) exposure for benzene of 1 ppm (3.25 mg/m³). There is no UK WEL screening value for naphthalene, however, the US Occupational Safety and Health Administration (OSHA) sets a Permissible Exposure limit (PEL) of 10 ppm (50 mg/m³) for naphthalene in workplace air (8 hour TWA). The National Institute for Occupational Safety and Health (NIOSH) 'immediately dangerous to life or health' (IDLH) screening value for naphthalene in air is 250 ppm.

A detailed air quality assessment was subsequently undertaken by Peak Environmental Solutions, to determine human health risk based vapour monitoring criteria for adjacent land users, taking into account adjacent and distal commercial, school and residential receptors, for the main earthworks proposed to be undertaken over a period of nominally 10 weeks. The assessment report was submitted to LLDC, Hackney Council and PHE for review, and a revised version of the report was submitted on 17 January 2019 to LLDC responding to queries raised on the initial review of the report. The screening values are influenced by the duration of the works; the longer the exposure, the lower the thresholds. A Technical Note was issued in April 2019 providing threshold values for works of 10, 15, 20 and 25 weeks, and was supplemented by a further Technical Note in December 2019 providing threshold values for 30, 40 and 52-week exposure. Tables 1a and 1b below summarise threshold values for 10, 25 and 40 week exposure:

| Table 1a – Passive Threshold-Uc Criteria in mg/m³ | | | | |
|---|--|----------------------|-------------------|---------------------|
| Substance | Passive Threshold-Uc in mg/m ³ 10-25-40 week exposure | | | |
| | Adjacent | Distal | | |
| | Commercial & Passer-by | Commercial | School | Residential |
| Naphthalene | 0.16-0.06-0.04** | 0.16-0.06-0.04** | 0.06-0.02-0.014** | 0.04-0.015-0.0094** |
| Sum TPH | 25-20-13 | 25-20-13 | 18-7-4.7 | 10-5-3.1 |
| Aliphatic TPH C5-C6 | Via Sum TPH | Via Sum TPH | Via Sum TPH | Via Sum TPH |
| Aliphatic TPH C6-8 | | | | |
| Aliphatic TPH C8-10 | | | | |
| Aliphatic TPH C10-12 | | | | |
| Aliphatic TPH C12-16 | | | | |
| Aromatic TPH C5-7 (threshold Benzene) | | | | |
| Aromatic TPH C7-8 (Toluene) | 7.4-4.1-2.6 | 7.4-4.1-2.6 | 1.8-0.8-0.5 | 1.3-0.54-0.34 |
| Aromatic TPH C8-C10 | | | | |
| Aromatic TPH C10-12 | | | | |
| Aromatic TPH C12-16 | 0.3-0.18-0.11 | 0.3-0.18-0.11 | 0.2-0.08-0.05** | 0.14-0.055-0.034** |
| Sum Methylnaphthalenes | | | | |
| Benzene | 0.19-0.11-0.067* | 0.19-0.11-0.067* | 0.13-0.05-0.032* | 0.09-0.035-0.022* |
| Toluene | Pragmatic 10-4.7-2.9 | Pragmatic 10-4.7-2.9 | 4-1.9-1.7 | 3-1.3-1.1 |
| Ethylbenzene | | | 1.7 | 1.1 |
| Sum Xylenes | | | 1.2 | 0.8 |
| Sum TMB | 0.14-0.08-0.05** | 0.14-0.08-0.05** | 0.04-0.02-0.01** | 0.03-0.01-0.0065** |

Notes: These thresholds take into account parameter CF-est where relevant (correction factor for time-weighted average concentrations).
* =Benzene Criteria for the residential receptor is approaching the UK AQS (0.005) so needs to be applied with caution.
** =Naphthalene, methylnaphthalene and TMB criteria are very low, so need to be applied with caution.

| Table 1b – Active Threshold-Uc Criteria in mg/m³ | | | | |
|--|---|----------------|-------------------|---------------------|
| Substance | Active Threshold-Uc in mg/m ³ 10-25-40 week exposure | | | |
| | Adjacent | Distal | | |
| | Commercial & Passer-by | Commercial | School | Residential |
| Naphthalene | 0.55-0.22-0.14 | 0.55-0.22-0.14 | 0.19-0.08-0.048** | 0.04-0.015-0.0094** |
| Sum TPH | 100-74-46 | 100-74-46 | 60-25-16 | 10-5-3.1 |
| Aliphatic TPH C5-C6 | Via Sum TPH | Via Sum TPH | Via Sum TPH | Via Sum TPH |
| Aliphatic TPH C6-8 | | | | |
| Aliphatic TPH C8-10 | | | | |
| Aliphatic TPH C10-12 | | | | |
| Aliphatic TPH C12-16 | | | | |
| Aromatic TPH C5-7 (threshold Benzene) | | | | |
| Aromatic TPH C7-8 (Toluene) | 35-14-15 | 35-14-9 | 6-2.7-1.7 | 1.3-0.54-0.34 |
| Aromatic TPH C8-C10 | | | | |
| Aromatic TPH C10-12 | | | | |
| Aromatic TPH C12-16 | 1.5-0.61-0.38 | 1.5-0.61-0.38 | 0.7-0.28-0.17 | 0.14-0.055-0.034 |
| Sum Methylnaphthalenes | | | | |
| Benzene | 0.9-0.37-0.23 | 0.9-0.37-0.23 | 0.44-0.18-0.11 | 0.09-0.035-0.022* |
| Toluene | Pragmatic 10 | Pragmatic 10 | Pragmatic 5-5-4 | 3-1.3-1.1 |
| Ethylbenzene | | | | 1.1 |
| Sum Xylenes | | | | 0.8 |
| Sum TMB | 0.45-0.27-0.17 | 0.45-0.27-0.17 | 0.13-0.053-0.033 | 0.03-0.01-0.0065** |

Notes: * =Benzene Criteria for the residential receptor is approaching the UK AQS (0.005) so needs to be applied with caution.
** =Naphthalene, methylnaphthalene and TMB criteria are very low, so need to be applied with caution.

The values in Table 1a are used in the assessment of results from the time-weighted average passive sorbent tube monitoring, while the values in Table 1b are relevant to comparison with active 'real-time' sampling using vacuum canisters, pumped sorbent tubes or other methods.

2. Fieldwork

The seventy-first round of monitoring discussed in this report was undertaken over a nine-day period between 22 May and 1 June 2020.

3. Laboratory Analysis

Cross reference between the laboratory test references and the sample locations is given in Table 3.

| Table 3 – Laboratory reference and sample location summary | |
|---|------------------------------------|
| Location | Laboratory sample reference |
| V1 | U205U |
| V2 | U203U |
| V3 | Z880M |
| V4 | Z876M |
| V5 | U207U |
| V6 | U201U |
| V7 | Z878M |
| V8 | Z879M |
| T1 | U206U |
| T2 | U204U |
| T3 | U202U |

The laboratory analysis included suites of both VOCs and SVOCs. The results were calculated as time-weighted average concentrations.

Concentrations of VOCs and SVOCs were all below the detection limit for the test method, of 1 µg/m³ (equivalent to 0.0003 ppm for benzene).

Threshold values are influenced by the duration of the exposure; thresholds will be lower for an extended earthworks period. Re-assessment will be undertaken as the works progress to ensure the thresholds remain protective.

It should be noted that the methods of test for VOC and SVOC are significantly different; VOC analysis is undertaken using headspace analysis while the SVOC analysis uses a solvent to desorb determinands from the sampling tube prior to analysis. Consequently there may be some variation in concentrations of determinands measured depending on the method of analysis.

Testing for speciated total petroleum hydrocarbons (TPH) was undertaken at two locations on the site boundary and one location at the school (Locations T1, T2 and T3). Locations T2 and T3 recorded concentrations to be below the detection limit for the test method of 100 µg/m³. Measurable concentrations of TPH were recorded only at location T1 on the site boundary, with a total concentration of 3550 µg/m³. This is however well below the screening threshold of 13000 µg/m³ for a commercial/passenger by receptor at 40 weeks exposure. Concentrations of VOC and SVOC at the same location were below the detection limit for the test method. The source of the TPH has not been identified but could potentially be associated with the use of powered site plant (e.g. petrol-powered cutters) or vehicular impact from Wallis Road.

4. Conclusions

Concentrations of VOC, SVOC and BTEX were well below the screening values adopted for assessment, as described in this letter report.

Monitoring will be maintained during active earthworks activities at the site, and will be reported nominally on a weekly basis.

Should you require any further information or assistance, please do not hesitate to contact us.



Yours sincerely
RSA Geotechnics Ltd



Adrian Phillips, FGS
Technical Director

Encs Passive Air Monitoring - Drawing Number 14862CO/2 Version B
Laboratory Test Reports (ELAB, 20-28343 & 57144)

Copy (Email) to: Jason Lumb (Arup) jason.lumb@arup.com
Jeff Widd (Arup) jeff.widd@arup.com
Hilary Wrenn (LLDC) hilarywrenn@londonlegacy.co.uk
LLDC lldc@arup.com
Stephen Pedro (Telford Homes) stephen.pedro@telfordhomes.london
Fintan Mooney (Telford Homes) fintan.mooney@telfordhomes.london
wallisroad@fourcommunications.com



| | |
|--|---|
| <p>PASSIVE AIR MONITORING (Based upon Google earth image)</p> <p>80 - 84 AND 88 WALLIS ROAD, HACKNEY WICK, E9 5LN</p> | <p>NOTE: All locations are approximate</p> <p>Date 8 MARCH 2019</p> |
| | <p>Scale NOT TO SCALE</p> |
| <p>RSA GEOTECHNICS LIMITED</p> | <p>Drawing No 14862CO/2 Version B</p> |



Unit A2
Windmill Road
Ponswood Industrial Estate
St Leonards on Sea
East Sussex
TN38 9BY
Telephone: (01424) 718618

cs@elab-uk.co.uk
info@elab-uk.co.uk

THE ENVIRONMENTAL LABORATORY LTD

Analytical Report Number: 20-28343

Issue: 1

Date of Issue: 10/06/2020

Contact: Adrian Phillips

Customer Details: RSA Geotechnics Ltd
Ashburnham House
1 Maitland Road
Needham Market
Suffolk IP6 8NZ

Quotation No: Q18-01116

Order No: 14862CO

Customer Reference: 14862CO

Date Received: 03/06/2020

Date Approved: 10/06/2020

Details: Wallis Road Air Monitoring 22 May to 1 June 2020

Approved by:

Mike Varley, Technical Manager

Any comments, opinions or interpretations expressed herein are outside the scope of UKAS accreditation (Accreditation Number 2683)

This report may only be reproduced in full



Sample Summary

Report No.: 20-28343, issue number 1

| Elab No. | Client's Ref. | Date Sampled | Date Scheduled | Description | Deviations |
|----------|---------------|--------------|----------------|-------------|------------|
| 205217 | U205U RT V1 | 01/06/2020 | 03/06/2020 | | |
| 205218 | U203U RT V2 | 01/06/2020 | 03/06/2020 | | |
| 205219 | Z880M RT V3 | 01/06/2020 | 03/06/2020 | | |
| 205220 | Z876M RT V4 | 01/06/2020 | 03/06/2020 | | |
| 205221 | U207U RT V5 | 01/06/2020 | 03/06/2020 | | |
| 205222 | U201U RT V6 | 01/06/2020 | 03/06/2020 | | |
| 205223 | Z878M RT V7 | 01/06/2020 | 03/06/2020 | | |
| 205224 | Z879M RT V8 | 01/06/2020 | 03/06/2020 | | |



Results Summary

Report No.: 20-28343, issue number 1

| | | | | ELAB Reference | 205217 | 205218 | 205219 | 205220 | 205221 | 205222 | 205223 | 205224 |
|-------------------------------|-------|-------|-----|--------------------|------------|------------|------------|------------|------------|------------|------------|------------|
| | | | | Customer Reference | RT V1 | RT V2 | RT V3 | RT V4 | RT V5 | RT V6 | RT V7 | RT V8 |
| | | | | Sample ID | | | | | | | | |
| | | | | Sample Type | GAS | GAS | GAS | GAS | GAS | GAS | GAS | GAS |
| | | | | Sample Location | U205U | U203U | Z880M | Z876M | U207U | U201U | Z878M | Z879M |
| | | | | Sample Depth (m) | | | | | | | | |
| | | | | Sampling Date | 01/06/2020 | 01/06/2020 | 01/06/2020 | 01/06/2020 | 01/06/2020 | 01/06/2020 | 01/06/2020 | 01/06/2020 |
| Determinand | Codes | Units | LOD | | | | | | | | | |
| VOC | | | | | | | | | | | | |
| MTBE | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Heptane | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Octane | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Nonane | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Benzene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Toluene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Ethylbenzene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| m+p-xylene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| o-xylene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| cis-1,2-dichloroethene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 1,1-Dichloroethane | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Chloroform | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Tetrachloromethane | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 1,1,1-Trichloroethane | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Trichloroethylene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Tetrachloroethylene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 1,1,1,2-Tetrachloroethane | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 1,1,2,2-Tetrachloroethane | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Chlorobenzene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Bromobenzene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Bromodichloromethane | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Methylethylbenzene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 1,1-Dichloro-1-propene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Trans - 1-2 -dichloroethylene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 2,2-Dichloropropane | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Bromochloromethane | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 1,2-Dichloroethane | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Dibromomethane | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 1,2-Dichloropropane | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| cis-1,3-Dichloro-1-propene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| trans-1,3-Dichloro-1-propene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 1,1,2-Trichloroethane | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Dibromochloromethane | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 1,3-Dichloropropane | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Dibromoethane | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Styrene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Propylbenzene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 2-Chlorotoluene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 1,2,4-Trimethylbenzene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 4-Chlorotoluene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| t-butylbenzene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 1,3,5-Trimethylbenzene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 1-methylpropylbenzene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| p-cymene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 1,3-Dichlorobenzene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Butylbenzene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 1,2-Dibromo-3-chloropropane | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Hexachlorobutadiene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 1-2-3 - Trichlorobenzene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Naphthalene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 1-2-4 - Trichlorobenzene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 1,4-Dichlorobenzene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 1,2-Dichlorobenzene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Bromoform | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |



Results Summary

Report No.: 20-28343, issue number 1

| | | | | ELAB Reference | 205217 | 205218 | 205219 | 205220 | 205221 | 205222 | 205223 | 205224 |
|-----------------------------|-------|-------|-----|--------------------|------------|------------|------------|------------|------------|------------|------------|------------|
| | | | | Customer Reference | RT V1 | RT V2 | RT V3 | RT V4 | RT V5 | RT V6 | RT V7 | RT V8 |
| | | | | Sample ID | | | | | | | | |
| | | | | Sample Type | GAS | GAS | GAS | GAS | GAS | GAS | GAS | GAS |
| | | | | Sample Location | U205U | U203U | Z880M | Z876M | U207U | U201U | Z878M | Z879M |
| | | | | Sample Depth (m) | | | | | | | | |
| | | | | Sampling Date | 01/06/2020 | 01/06/2020 | 01/06/2020 | 01/06/2020 | 01/06/2020 | 01/06/2020 | 01/06/2020 | 01/06/2020 |
| Determinand | Codes | Units | LOD | | | | | | | | | |
| SVOC | | | | | | | | | | | | |
| Phenol | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Aniline | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Bis(2-chloroethyl)ether | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 2-Chlorophenol | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 1,3-Dichlorobenzene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 1,4-Dichlorobenzene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Benzyl Alcohol | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 1,2-Dichlorobenzene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 2-Methylphenol | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Bis(2-chloroisopropyl)ether | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 3 and 4-methylphenol | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| N-Nitrosodi-n-propylamine | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Hexachloroethane | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Nitrobenzene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Isophorone | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 2-Nitrophenol | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 2,4-Dimethylphenol | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Bis(2-chloroethoxy)methane | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 2,4-Dichlorophenol | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 1,3,5-Trichlorobenzene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Naphthalene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 3-Chloroaniline | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Hexachloro-1,3-butadiene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 4-Chloro-3-methylphenol | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 2-Methylnaphthalene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 1-Methylnaphthalene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Hexachlorocyclopentadiene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 2,4,6-Trichlorophenol | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 2,4,5-Trichlorophenol | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 1-Chloronaphthalene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 2-Nitroaniline | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 1,4-Dinitrobenzene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Dimethyl phthalate | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 1-3-dinitrobenzene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 2-6-dinitrotoluene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Acenaphthylene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 1,2-Dinitrobenzene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 3-Nitroaniline | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Acenaphthene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 4-nitrophenol | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Dibenzofuran | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 2,3,5,6-Tetrachlorophenol | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 2,3,4,6-Tetrachlorophenol | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Diethyl phthalate | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 1-chloro-4-phenoxybenzene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Fluorene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 4-Nitroaniline | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Dinitro-o-cresol | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Diphenylamine | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Azobenzene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| 1-bromo-4-phenoxybenzene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Hexachlorobenzene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Pentachlorophenol | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Phenanthrene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Anthracene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Carbazole | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Dibutyl phthalate | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Fluoranthene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Pyrene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Butyl benzyl phthalate | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Bis-2-ethylhexyladipate | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Diisooctyl phthalate | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Benzo(a)anthracene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Chrysene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Bis(2-ethylhexyl)phthalate | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Benzo(b)fluoranthene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Benzo(k)fluoranthene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Benzo(a)pyrene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Indeno(1,2,3-CD)pyrene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Dibenz(ah)anthracene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Benzo(ghi)perylene | N | µg/m3 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |



Method Summary

Report No.: 20-28343, issue number 1

| Parameter | Codes | Analysis Undertaken On | Date Tested | Method Number | Technique |
|--------------|-------|------------------------|-------------|---------------|-----------|
| SVOC - Tubes | N | | 03/06/2020 | 167 | GC-MS |
| VOC - Tubes | N | | 03/06/2020 | 181 | GC-MS |

Tests marked N are not UKAS accredited



Report Information

Report No.: 20-28343, issue number 1

Key

| | |
|-----|---|
| U | hold UKAS accreditation |
| M | hold MCERTS and UKAS accreditation |
| N | do not currently hold UKAS accreditation |
| ^ | MCERTS accreditation not applicable for sample matrix |
| * | UKAS accreditation not applicable for sample matrix |
| S | Subcontracted to approved laboratory UKAS Accredited for the test |
| SM | Subcontracted to approved laboratory MCERTS/UKAS Accredited for the test |
| NS | Subcontracted to approved laboratory. UKAS accreditation is not applicable. |
| I/S | Insufficient Sample |
| U/S | Unsuitable sample |
| n/t | Not tested |
| < | means "less than" |
| > | means "greater than" |

Soil sample results are expressed on an air dried basis (dried at < 30°C), and are uncorrected for inert material removed.

ELAB are unable to provide an interpretation or opinion on the content of this report.

The results relate only to the sample received.

PCB congener results may include any coeluting PCBs

Uncertainty of measurement for the determinands tested are available upon request

Unless otherwise stated, sample information has been provided by the client. This may affect the validity of the results.

Deviation Codes

- | | |
|---|--|
| a | No date of sampling supplied |
| b | No time of sampling supplied (Waters Only) |
| c | Sample not received in appropriate containers |
| d | Sample not received in cooled condition |
| e | The container has been incorrectly filled |
| f | Sample age exceeds stability time (sampling to receipt) |
| g | Sample age exceeds stability time (sampling to analysis) |

Where a sample has a deviation code, the applicable test result may be invalid.

Sample Retention and Disposal

All soil samples will be retained for a period of one month

All water samples will be retained for 7 days following the date of the test report

Charges may apply to extended sample storage



Unit A2
Windmill Road
Ponswood Industrial Estate
St Leonards on Sea
East Sussex
TN38 9BY
Telephone (01424) 718618
Facsimile (01424) 729911

THE ENVIRONMENTAL LABORATORY LTD

Adrian Phillips
RSA Geotechnics Ltd
1 Maitland Road
Needham Market
Suffolk, IP6 8NZ

Reporting Date: 10 June 2020

ANALYTICAL REPORT No. 57144

Samples Received By: Laboratory Courier
Sample Receipt Date: 03/06/20
Your Job No: 14862CO
Your Order No: 14862CO
Site Location: Wallis Road Air Monitoring 22 May to 1 June 2020
No Samples Received: 3
Date of Sampling: 01/06/20

This report was written by: Stuart Ballard

Authorised By;

Mike Varley
Technical Manager (BSc, CChem
CSci, FRSC)

Any comments, opinions or interpretations expressed herein are outside the scope of UKAS accreditation (Accreditation Number 2683)

THE ENVIRONMENTAL LABORATORY LTD

Unit A2, Windmill Road, Ponswood Industrial Estate, St Leonards On Sea, East Sussex, TN38 9BY

Tel: 01424 718618 Fax: 01424 729911

ANALYTICAL REPORT No. 57144

Location: Wallis Road Air Monitoring 22 May to 1 June 2020



Your Job No: 14862CO
Your Order No: 14862CO
Reporting Date: 10/06/20

F.A.O. Adrian Phillips
RSA Geotechnics Ltd
1 Maitland Road
Needham Market
Suffolk, IP6 8NZ

TPH CWG - Tubes

| Characteristic | TUBE | TUBE | TUBE |
|---|----------------------|---------------|---------------|
| Date Sampled | 01/06/20 | 01/06/20 | 01/06/20 |
| TP/BH | U206U - RT T1 | U204U - RT T2 | U202U - RT V3 |
| Our ref | 38657 | 38658 | 38659 |
| <u>Aromatic</u> | | | |
| >EC ₅ -EC ₇ | (µg/m ³) | <100 | <100 |
| >EC ₇ -EC ₈ | (µg/m ³) | <100 | <100 |
| >EC ₈ -EC ₁₀ | (µg/m ³) | 1047 | <100 |
| >EC ₁₀ -EC ₁₂ | (µg/m ³) | 499 | <100 |
| >EC ₁₂ -EC ₁₆ | (µg/m ³) | <100 | <100 |
| >EC ₁₆ -EC ₂₁ | (µg/m ³) | <100 | <100 |
| >EC ₂₁ -EC ₃₅ | (µg/m ³) | <100 | <100 |
| >EC ₃₅ -EC ₄₀ | (µg/m ³) | <100 | <100 |
| <u>Aliphatic</u> | | | |
| >EC ₅ -EC ₆ | (µg/m ³) | <100 | <100 |
| >EC ₆ -EC ₈ | (µg/m ³) | <100 | <100 |
| >EC ₈ -EC ₁₀ | (µg/m ³) | 1387 | <100 |
| >EC ₁₀ -EC ₁₂ | (µg/m ³) | 618 | <100 |
| >EC ₁₂ -EC ₁₆ | (µg/m ³) | <100 | <100 |
| >EC ₁₆ -EC ₂₁ | (µg/m ³) | <100 | <100 |
| >EC ₂₁ -EC ₃₅ | (µg/m ³) | <100 | <100 |
| >EC ₃₅ -EC ₄₀ | (µg/m ³) | <100 | <100 |
| TPH (C ₅ - C ₄₀) | (µg/m ³) | 3550 | <100 |

All results expressed on dry weight basis

** - MCERTS accredited test

Stuart Ballard



Unit A2
Windmill Road
Ponswood Industrial Estate
St Leonards on Sea
East Sussex
TN38 9BY
Telephone (01424) 718618
Facsimile (01424) 729911

THE ENVIRONMENTAL LABORATORY LTD

SAMPLE RECEIPT AND TEST DATES

Our Analytical Report Number 57144
Your Ref No: 14862C0
Sample Receipt Date: 03/06/20
Reporting Date: 10/06/20

Registered: 03/06/20
Prepared: 04/06/20
Analysis complete: 10/06/20

TEST METHOD SUMMARY

| PARAMETER | Analysis Undertaken on | Date Tested | Method Number | Technique |
|--------------------------|---------------------------|-------------|------------------|--------------------|
| Carbon Banding (TPH CWG) | As submitted sample | 02/06/20 | 214 | Gas chromatography |

Note:- Documented In-house procedure based on HSG 248 2005

** - MCERTS Accredited test

Determinands not marked with * or ** are not accredited

MCERTS accreditation covers samples which are predominantly sand, clay, loam or combinations of these three soil types

Any comments, opinions, or interpretations expressed herein are outside the scope of UKAS accreditation (Accreditation Number 2683)
